BRUHAT BANGALORE MAHANAGAR PALIKE

Project Division, Yelahanka Zone

SCHEDULE - B

BBMP/2018-19/OW/WORK_INDENT34581

Maintenance of Crematorium Burrial Ground and Office maintenance in ward no.03

SNo	Quantity	Item Name	Unit	Rates quoted by Sri. S SOMASHEKAR	
				In figures	In words
1	0.60	Clearing and grubbing road land including uprooting rank vegetation, grass, bushes, shrubs, saplings and trees girth up to 300mm, removal of stumps of trees cut earlier and disposal of unserviceable materials and stacking of serviceable material to be used or auctioned, including removal and disposal of top organic soil not exceeding 150 mm in thickness complete as per specifications. I. By Manual Means: A. In area of light jungle.	Ha	85000.00	Rupees Eighty Five Thousand Only
2	534.00	Earthwork excavation by manual means for roads, drains & similar works in ordinary soil excavated surface levelled and sides neatly dressed, the disposed earth to be levelled neatly after breaking of clods complete as per specifications.	Cum	250.00	Rupees Two Hundred Fifty Only
3	5.00	Providing and fixing granite benches as per design, specification and fixing as per the directions of the engineer in charge.	Unit	12000.00	Rupees Twelve Thousand Only
6		GST @ 12%			

Somasekhar
Contractor

Executive Engineer
Project Division
Yelahanka Zone

8/5/19